

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-24281-00-00  
Spot: SENWSENE Sec/Twnshp/Rge: 30-10S-17W  
1787 feet from N Section Line, 967 feet from E Section Line  
Lease Name: JONES Well #: 1-30  
County: ROOKS Total Vertical Depth: 3771 feet

Operator License No.: 30717  
Op Name: DOWNING-NELSON OIL CO INC  
Address: PO BOX 1019  
HAYS, KS 67601

<u>String</u>	<u>Size</u>	<u>Depth (ft)</u>	<u>Pulled (ft)</u>	<u>Comments</u>
SURF	8.625	220		150 sx

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/31/2015 12:00 AM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 305 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB WitnessType: NONE  
Date/Time Plugging Completed: 01/31/2015 7:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

1st plug @3660 w/50 sx  
2nd plug @1381 w/50 sx  
3rd plug @810 w/100 sx  
4th plug @270 w/50 sx  
5th plug @40 w/10 sx  
  
Rathole 30 sx Mousehole 15 sx


Remarks: ALLIED

Plugged through: DP

MAR 04 2015 *CKM*

District: 04

Signed \_\_\_\_\_



(TECHNICIAN)

*CKM*

KCC WICHITA

FEB 25 2015

RECEIVED

FEB 18 2015