

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-20552-00-00
Spot: SESWSW Sec/Twnshp/Rge: 15-13S-18W
270 feet from S Section Line, 4290 feet from E Section Line
Lease Name: BRAUN A Well #: 3
County: ELLIS Total Vertical Depth: 3634 feet

Operator License No.: 34506
Op Name: EMPIRE ENERGY E&P, LLC
Address: 345 RIVERVIEW ST., STE 540
WICHITA, KS 67203

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3634		150 SX
SURF	8.625	557		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/19/2015 9:00 AM
Plug Co. License No.: 34272 Plug Co. Name: OUTLAW WELL SERVICE LLC
Proposal Rcvd. from: RANDY WEIGEL Company: EMPIRE ENERGY LLC Phone: (785) 737-3736

Proposed Plugging Method: Ordered 385 sx 60/40 pozmix 4% gel cement, 12 sx gel and 500 # hulls. Knocked out CIBP at 3564'. Casing leaks 0' - 1100'. Arb- 3614' - 3629'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/19/2015 12:30 PM KCC Agent: PAT STAAB

KCC WICHITA
MAR 02 2015
RECEIVED

Actual Plugging Report:

Perf Tech shot holes at 1850', 1367' and 500'. Outlaw Well Service ran in hole with tubing to 3581'. Quality rigged to tubing and mixed and pumped 12 sx gel followed by 50 sx cement w/250 # hulls mixed in. Pulled tubing to 1850' and pumped 250 sx cement w/250 # hulls mixed in to circulate cement up 5 1/2" casing. Pulled tubing. Rigged to 5 1/2" casing with a swedge and pumped 50 sx cement on 5 1/2" casing at 200 psi. Shut in pressure 150 psi. Rigged to 8 5/8" casing and pumped 35 sx cement at 185 psi. Shut in pressure 150 psi.

GPS: 38.91519N -099.31349W
235' FSL 4200' FEL
SE SE SW SW

Perfs:


Remarks: QUALITY OILWELL CEMENTING TICKET # 1213

Plugged through: TBG

MAR 04 2015
CKM

District: 04

Signed



(TECHNICIAN)

CM

FEB 20 2015