

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-24178-00-00
Spot: W2NENENW Sec/Twnshp/Rge: 33-19S-14W
4950 feet from S Section Line, 3270 feet from E Section Line
Lease Name: MCKINNEY Well #: 1
County: BARTON Total Vertical Depth: 3575 feet

Operator License No.: 7383
Op Name: GRADY BOLDING CORPORATION
Address: 114 NORTH MAIN P.O. BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2335	1500	200 SX
SURF	8.625	950		400 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/29/2015 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: GRADY BOLDING Company: GRADY BOLDING CORPORATION Phone: (620) 564-2240

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/29/2015 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped with cement. Cut casing at 1506'. Pulled casing to 1500' and pumped 125 sx cement w/200 # hulls. Pulled casing to 900' and pumped 60 sx cement w/100 # hulls. Pulled casing to 600' and pumped 40 sx cement w/100 # hulls. Pulled casing to 300'. Circulated cement to surface with 105 sx cement. Pulled casing. Hole stayed full.

GPS: 38.36085 -098.87736

Perfs:

Top	Bot	Thru	Comments
1758	1760		
1741	1745		
1733	1737		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

MAR 04 2015 *CRM*

District: 04

Signed Bruce Rodie

KCC WICHITA (TECHNICIAN) *CM*

FEB 18 2015

RECEIVED

Form CP-2/3

FEB 04 2015