

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-109-21075-00-00
Spot: SWSWNENE Sec/Twnshp/Rge: 26-12S-32W
1235 feet from N Section Line, 1050 feet from E Section Line
Lease Name: G. ANDERSEN Well #: 5-26
County: LOGAN Total Vertical Depth: 4750 feet

Operator License No.: 9855
Op Name: GRAND MESA OPERATING COMPANY
Address: 1700 N WATERFRONT PKWY BLDG 600
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7.875	4745		175 SX
SURF	8.625	214		165 sx
T1	2.875	4707		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/18/2015 11:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOHN JOHNSON Company: GRAND MESA OPERATING CO Phone: (620) 617-3357

Proposed Plugging Method: Ordered 360 sx 60/40 pozmix 4% gel cement, 15 sx gel and 300 # hulls.
8 5/8" surface casing set at 214' w/165 sx cement. 5 1/2" production casing set at 4745' w/175 sx cement. DV Tool set at 2545' w/300 sx cement. TD 4750', PBD 4734'. Perforations: 4605' - 4609'. Well is non-commercial.

Plugging Proposal Received By: CASE MORRIS
Date/Time Plugging Completed: 02/18/2015 12:45 PM

Witness Type: COMPLETE (100%)
KCC Agent: DARREL DIPMAN

KCC WIC
MAR 02 2015
RECEIVED

Actual Plugging Report:

Connected to 5 1/2" production casing. Pumped 50 sx cement w/150 # hulls followed by 15 sx gel and 310 sx cement w/150 # hulls. Pressured to 500 psi. Connected to 8 5/8" surface casing and pumped 15 sx cement. Pressure to 300 psi.

GPS: 38.98602N -100.83620W

Perfs:

Top	Bot	Thru	Comments
4605	4609		

Remarks: SWIFT SERVICES TICKET # 27,132

Plugged through: CSG

MAR 04 2015 *JKM*

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

FEB 19 2015