

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-039-20942-00-00  
Spot: NESW Sec/Twnshp/Rge: 16-5S-26W  
1980 feet from S Section Line, 1980 feet from W Section Line  
Lease Name: STEPHENS Well #: 11-16  
County: DECATUR Total Vertical Depth: 3910 feet

Operator License No.: 33629  
Op Name: GREAT PLAINS ENERGY, INC.  
Address: 6121 S 58TH ST, STE B  
LIN COLN, NE 68516

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3729		
PROD	5.5	3909		435 SX
SURF	8.625	318		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/16/2015 10:00 AM  
Plug Co. License No.: 33755 Plug Co. Name: QUALITY PLUS OILFIELD SERVICES, LLC  
Proposal Rcvd. from: JOHN MONDERO Company: GREAT PLAINS ENERGY INC. Phone: (785) 475-7245

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 7 sx gel and 500 # hulls.  
8 5/8" surface casing set at 318' w/200 sx cement. 5 1/2" production casing set at 3909' w/110 sx cement. TD 3910',  
PBTD3904'. Perforations: 3833' - 3835', 3815' - 3822', 3765' - 3770'. CIBP set at 3729'. Open perforations: 3694' - 3700'.  
Stage collar set at 2237' w/325 sx cement

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/16/2015 1:30 PM KCC Agent: DARREL DIPMAN

KCC WICHITA  
MAR 02 2015  
RECEIVED

Actual Plugging Report:

Ran tubing to 3650' and pumped 7 sx gel followed by 65 sx cement w/200 # hulls. Pulled tubing to 2215' and pumped 110 sx cement w/150 # hulls. Pulled tubing to 1100' and pumped 125 sx cement w/100 # hulls. Circulated cement to surface. Pulled tubing to surface. Topped w/40 sx cement. Casing full of cement. Connected to 8 5/8" surface casing and pumped 20 sx cement. Maximum pressure 300 psi.

GPS: 39.61600N -100.24805W

Perfs:

Top	Bot	Thru	Comments
3833	3835		
3815	3822		
3765	3770		
3734	3740		
3694	3700		

Remarks: SWIFT CEMENT SERVICES TICKET # 27128

Plugged through: TBG

MAR 04 2015 CM

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM

FEB 18 2015