

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-10207-00-00
Spot: SESESW Sec/Twnshp/Rge: 17-22S-33W
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: GARDEN CITY B Well #: 1
County: FINNEY Total Vertical Depth: 4830 feet

Operator License No.: 32158
Op Name: H & B PETROLEUM CORP.
Address: PO BOX 277
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2500		WITH 2 SX CMT
DVT		2760		
PROD	5.5	4830	0	
SURF	8.625	302		WITH 275 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/06/2015 10:00 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: MICK HITSCHMAN Company: H & B PETROLEUM Phone: (620) 564-3002

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/09/2015 11:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

2/6/15: TAG PBTD AT 2553'. CIBP @ 2500' WITH 2 SX CMT. RAN CBL FROM 2400' TO 10'. TOP OF GOOD CMT AT 1454'. TOP OF LIGHT CMT AT 546'. PERFORATE AT 340'. INJECTION RATE 2 BPM @ 280#. FLUID CIRCULATING TO SURFACE. 2/9/15: RUN TBG TO 1969' & SPOT 30 SX CMT. PULL TO 1082' & CIRCULATE CMT TO SURFACE IN THE 5 1/2" CASING WITH 110 SX CMT. CIRCULATE CMT TO SURFACE FROM 340' TO 0' IN THE 5 1/2" X 8 5/8" ANNULUS USING 110 SX CMT. TOP OFF 5 1/2" WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2540	2563		

KCC WICHITA
MAR 02 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY GLOBAL.

Plugged through: TBG

MAR 04 2015 *EXM*

District: 01

Signed _____

Ken Jehlik
(TECHNICIAN)

RECEIVED
FEB 13 2015
KCC DODGE CITY *MP*

SP