

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-22765-00-00
Spot: NWSEW Sec/Twnshp/Rge: 3-7S-20W
3630 feet from S Section Line, 3630 feet from E Section Line
Lease Name: WALLER Well #: 2
County: ROOKS Total Vertical Depth: 3672 feet

Operator License No.: 8914
Op Name: H & C OIL OPERATING INC.
Address: PO BOX 86
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3657		500 SX
SURF	8.625	341		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/22/2015 10:30 AM
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC
Proposal Rcvd. from: BOB PLANTE Company: H & C OIL OPERATING INC. Phone: (785) 434-7434

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Clean out to 3610'.
Production perforations: 3565' - 3672'
Knock out CIBP at 3298'

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/22/2015 1:45 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3585' and pumped 180 sx cement w/250 # hulls. Pulled tubing to 1784' and pumped 140 sx cement w/250 # hulls to circulate cement to surface. Pulled all tubing. Topped off 5 1/2" casing w/30 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pressured to 300 psi immediately.

GPS: 39.47620N -099.54119W

Perfs:

Top	Bot	Thru	Comments
3609	3615		
3579	3586		
3565	3569		

Remarks: QUALITY OILWELL CEMENTING TICKET # 1201

Plugged through: TBG

MAR 04 2015 *CKM*

District: 04

Signed Pat Bedore
(TECHNICIAN)

CM

KCC WICHITA

FEB 18 2015

RECEIVED

JAN 30 2015