

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-22841-00-00  
Spot: SENWSWNW Sec/Twnshp/Rge: 3-7S-20W  
3510 feet from S Section Line, 4900 feet from E Section Line  
Lease Name: WALLER Well #: 6  
County: ROOKS Total Vertical Depth: 3704 feet

Operator License No.: 8914  
Op Name: H & C OIL OPERATING INC.  
Address: PO BOX 86  
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3660		450 SX
SURF	8.625	343		225 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/16/2015 2:30 PM  
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC  
Proposal Rcvd. from: BOB PLANTE Company: H & C OIL OPERATING Phone: (785) 434-7434

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Production perforations: 3566' - 3585'  
Fish stuck in hole at 3305'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/19/2015 4:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran depthometer to 3063'. Ran sand pump in hole and cleaned out to top of fish at 3305'. Ran tubing to 3273' and pumped 180 sx cement w/250 # hulls. Pulled tubing to 1803' and pumped 180 sx cement w/250 # hulls. Lost circulation and pressure. Pressured to 1200 psi. Tried to pull tubing out and it was stuck at approximately 15' - 20' out. Worked tubing and could not get loose. Shut down for the weekend.  
01/19/2015- Perforated tubing at 330' and pumped 50 sx cement down tubing to circulate cement to surface. Shut in to pressure. Split 5 1/2" casing above braiden head.  
01/19/2015- Hooked to 8 5/8" x 5 1/2" annulus and pumped 5 sx cement. Pressured to 300 psi.  
GPS: 39.47614N -099.54575W

Perfs:

Top	Bot	Thru	Comments
3582	3585		
3572	3574		
3566	3568		

Remarks: QUALITY OIL WELL CEMENTING

Plugged through: TBG

MAR 04 2015 *CKM*

District: 04

Signed \_\_\_\_\_

*Pat Bedore*

(TECHNICIAN)

*CM*

KCC WICHITA

FEB 18 2015

RECEIVED

JAN 30 2015