

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-171-20461-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 15-19S-34W
994 feet from S Section Line, 2336 feet from E Section Line
Lease Name: ROBINSON Well #: 3-15
County: SCOTT Total Vertical Depth: 4845 feet

Operator License No.: 33885
Op Name: HEAT WAVES HOT OIL SERVICE LLC
Address: 501 S CHERRY ST, STE 320
DENVER, CO 80246

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4440		WITH 2 SX CMT
PC		1508		WITH 200 SX CMT
PROD	5.5	4844	0	WITH 350 SX CMT
SURF	8.625	216		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/11/2015 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: RON OSTERBUHR Company: _____ Phone: _____

Proposed Plugging Method: CIBP WITH 2 SX CMT OR 25 SX CMT & HULLS AT 4440'. PERFORATE AT 2280'. RUN TBG TO 2300' & SPOT 75 SX CMT WITH 200# HULLS IN LAST 30 SX CMT IN 2 STAGES. PULL TO 1300' & CIRCULATE CMT TO SURFACE WITH 130 SX CMT. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/12/2015 9:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TOP OF TBG & ROD FISH IN HOLE IS 4460'. SET CIBP @ 4440' WITH 2 SX CMT. PERFORATE AT 2280'. RUN TBG TO 2300' & SPOT 75 SX CMT WITH 200# HULLS. PULL TBG TO 1291' & CIRCULATE CMT TO SURFACE WITH 150 SX CMT. TOOH WITH TBG & TOP OFF WITH 60 SX CMT. PUMP 15 SX CMT DOWN THE ANNULUS TO 200#. 2/12/15: TAG TOC @ 38' IN 5 1/2" CASING. TOP OFF WITH SACK CMT.

Perfs:

Top	Bot	Thru	Comments
4760	4768		

KCC WICHITA
MAR 02 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

MAR 04 2015 *ckm*

District: 01

Signed



(TECHNICIAN)

RECEIVED
FEB 23 2015
KCC DODGE CITY

