

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-22585-00-00
Spot: E2NWSE Sec/Twnshp/Rge: 20-15S-22W
2045 feet from S Section Line, 1630 feet from E Section Line
Lease Name: JUNE B Well #: 1
County: TREGO Total Vertical Depth: 4294 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4291		350 SX
SURF	8.625	219		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/12/2015 12:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: BRYAN HESS Company: WHITETAIL CRUDE, INC Phone: (620) 241-4640

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 15 sx gel and 500 # hulls.
DV Tool at 1590' w/200 sx cement.
Perforations at 4194' - 4207'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/12/2015 4:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4226' and pumped 15 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 2227' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1223' and pumped 140 sx cement. Good circulation of cement. Pulled tubing out. Topped off w/15 sx cement full. Tied on to backside and squeezed w/5 sx cement. Shut in at 200 psi.

GPS: 38.73116 -099.78870

Perfs:


Top	Bot	Thru	Comments
4203	4207		
4194	4207		

Remarks: SWIFT CEMENT TICKET # 28284

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

KCC WICHITA

FEB 18 2015

RECEIVED

MAR 04 2015 CM

FEB 13 2015