

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-24777-00-00
Spot: E2SWNW Sec/Twnshp/Rge: 16-19S-14W
1980 feet from N Section Line, 990 feet from W Section Line
Lease Name: CANFIELD Well #: 1
County: BARTON Total Vertical Depth: 3619 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3619		150 SX
SURF	8.625	832		150 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/06/2014 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L. D. DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement.
CIBP set over Arbuckle and CIBP set below shallow gas zone at 1810' DV Tool 1887'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/06/2014 12:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1350' and 800'. Ran tubing to 1755' and pumped 90 sx cement w/150 # hulls.
Pulled tubing to 800'. Circulated cement to surface on casing w/100 sx cement. Circulated
cement to surface on surface pipe w/90 sx cement. Pulled tubing. Topped off w/10 sx cement.

GPS: 38.39985 -098.88144

Perfs:

Top	Bot	Thru	Comments
3543	3546		
3360	3360		PLUG
3306	3312		
1768	1776		
1749	1759		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

MAR 04 2015 *CM*

District: 04

Signed Bruce Rodie
(TECHNICIAN) *CM*

KCC WICHITA

FEB 06 2015

FEB 18 2015

RECEIVED