

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-23823-00-01
Spot: SENWSW Sec/Twnshp/Rge: 14-16S-14W
1650 feet from S Section Line, 4290 feet from E Section Line
Lease Name: BITTER Well #: 1-SWD
County: BARTON Total Vertical Depth: 3475 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3473		100 SX
SURF	8.625	467		215 SX

Well Type: SWD UIC Docket No: D24725.0 Date/Time to Plug: 12/01/2014 11:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS Phone: (214) 219-8883

Proposed Plugging Method: Emergency plug. Rig over hole. Junk in hole at 1920'. Will plug from this depth. Ordered 300 sx 60/40 pozmix 4% gel cement w/ 400 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/01/2014 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perforated at 1450', 920' and 450'. Ran tubing to 1900' and pumped 80 sx cement. Pulled tubing to 920'. Circulated cement to surface w/150 sx cement. Pulled tubing and topped off w/25 sx cement.
GPS: 38.65680 -098.84568

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

MAR 04 2015 *cm*

District: 04

Signed Bruce Rodie
(TECHNICIAN) *cm*

KCC WICHITA

FEB 18 2015

cc: uic/

DEC 22 2014

RECEIVED