

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-24986-00-00
Spot: S2S2SW Sec/Twnshp/Rge: 17-16S-14W
530 feet from S Section Line, 1290 feet from W Section Line
Lease Name: ELSASSER Well #: 1
County: BARTON Total Vertical Depth: 3520 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3514	1406	135 SX
SURF	8.625	435		225 SX
T1	2.875	3485		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/29/2015 11:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS Phone: (214) 219-8883

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/29/2015 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Cut casing at 1406'. Pulled casing to 1400' and pumped 125 sx cement w/200 # hulls. Pulled casing to 900' and pumped 50 sx cement w/100 # hulls. Pulled casing to 600' and pumped 40 sx cement w/100 # hulls. Pulled casing to 300'. Circulated cement to surface w/100 sx cement. Pulled casing and hole stayed full.

GPS: 38.65366 -098.89961

Perfs:

Top	Bot	Thru	Comments
3466	3470		

Remarks: QUALITY OILWELL CEMENTING TICKET # 1206

Plugged through: CSG

MAR 04 2015 *CKM*

District: 04

Signed Bruce Rodie
(TECHNICIAN) *CM*

KCC WICHITA

FEB 03 2015

FEB 18 2015

RECEIVED