

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25343-00-01
Spot: SESWNWSW Sec/Twnshp/Rge: 28-17S-15W
1560 feet from S Section Line, 370 feet from W Section Line
Lease Name: STOSS-NEELAND UNIT Well #: 1
County: BARTON Total Vertical Depth: 3632 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3627	2502	185 SX
SURF	8.625	1031		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/28/2015 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS Phone: (214) 219-8883

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/28/2015 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Cut casing at 2502'. Pulled casing to 1500' and pumped 125 sx cement w/200 # hulls. Pulled casing to 900' and pumped 50 sx cement w/100 # hulls. Pulled casing to 600' and pumped 40 sx cement w/100 # hulls. Pulled casing to 400'. Circulated cement to surface with 120 sx cement. Pulled casing and hole stayed full.

GPS: 38.54081 -098.99519

Perfs:

Top	Bot	Thru	Comments
3578	3582		

Remarks: QUALITY OILWELL CEMENTING TICKET # 1204

Plugged through: CSG

MAR 04 2015 *cm*

District: 04

Signed Bruce Rodie
(TECHNICIAN) *CM*

KCC WICHITA

FEB 18 2015

RECEIVED

FEB 03 2015