

API NUMBER 15-025-20497-0000

LEASE NAME Klinger

WELL NUMBER 1-2

TYPE OR PRINT
 NOTICE: Fill out completely and return
 to Cons. Div. office within 30 days.

1980 Ft. from S/N Line of Section (circle one)

660 Ft. from E/W Line of Section (circle one)

LEASE OPERATOR Kaiser-Francis Oil Company

SPOT LOCATION - C - NE - SE

ADDRESS P. O. Box 21468

SEC. 2 TWP. 34S S. RGE 25 (E) or (W)

CITY, STATE, ZIP Tulsa, OK 74121-1468

COUNTY Clark

PHONE#(918) 491-4314 OPERATORS LICENSE NO. 6568

Date Well Completed 9/11/81

Charater of Well Gas
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced 6/8/95

Date Plugging Completed 6/12/95

The plugging proposal was approved on n/a (date)

by Steve Durant (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? -

Producing Formation(s) Chester Depth to Top 5503 Bottom 5536 T.D. 5900

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Chester	Gas	5503	5536	8 5/8	639	-0-
				4 1/2	5899	4040

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

CIBP @ 5450' w/2 sxs cmt on top. Pumped 50 sxs cmt from 1150'-1050'. Pumped 50 sxs cmt from 659'-559'. Pumped 10 sxs cmt from 40'-surface. Cut off 8 5/8" 3' below ground level & cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service

License No. 6547

Address P. O. Box 506, Liberal, KS 67905-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator or (Operator) of above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Jan Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 31st day of July, 19 95

Richard J. Tuboff
 Notary Public

My Commission Expires: 12-23-97

RECEIVED
 STATE CORPORATION COMMISSION

AUG 02 1995

CONSERVED BY
 WICHITA KANSAS

WELL LOG

COMPANY Mesa Petroleum Company

SEC. 2-34S-25W

FARM Klinger

NO. 1-2

LOC. C S/2

TOTAL DEPTH 5900

COUNTY Clark, Kansas


COMM. 8-13-81

COMP. 8-24-81

CONTRACTOR

Zenith Drilling Corporation

^{CASING}
639' of 8 5/8", 24#, J55 casing, cemented
with 470 sacks cement
5899' of 4 1/2", 10.5#, K55 casing, cemented
with 300 sacks cement



ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

40	Soil & Sand
640	Sand & Red Bed
5900	Lime & Shale

RECEIVED

OCT 12 1981

AMARILLO PRODUCTION

State of Kansas }
 County of Sedgwick } ss

I, Emmet E. Hall of Zenith Drilling Corporation

upon oath state the above and foregoing is a true and correct copy of the log of the Klinger #1-2 well.

Emmet E. Hall

Subscribed and sworn to before me this 31st day of August, 1981.

My Commission Expires: August 15, 1983

Myrna D. Murphy
 Myrna D. Murphy NOTARY PUBLIC

RECEIVED
 STATE CORPORATION COMMISSION
 APR 27 1995
 CONSERVATION DIVISION
 WICHITA, KANSAS