

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-025-20,951-0000

LEASE NAME Isenbart 27

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2310 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 27 TWP. 34S RGE. 24W (E) or (W)

LEASE OPERATOR Cobra Oil & Gas Corporation

ADDRESS P.O.Box 1929 Woodward, Oklahoma 73802-1929 COUNTY Clark

PHONE#(405) 254-2027 OPERATORS LICENSE NO. 8802 Date Well Completed 7-9-86

Character of Well gas Plugging Commenced 10-22-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging Completed 10-27-92

The plugging proposal was approved on 10-16-92 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Chester Depth to Top 5556 Bottom 5590 T.D. 5800

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Chester	Gas	5556	5590	20"	90'	0
				8 5/8	735	0
				4 1/2	5799	3836

RECEIVED

Describe in detail the manner in which the well was plugged, indicating where the plug was placed and the method or methods used in introducing it into the hole. If other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Pump 50 sks. of cement from 1000 to 900

Pump 50 sks. of cement from 760 to 660

Put 10 sks. of cement from 40 to 0

Cut off & cap 8 5/8 3' below ground level

(If additional description is necessary, use BACK of this form.)

NOV 12 1992

CONSERVATION DIVISION
WICHITA, KS

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O.Box 506 Liberal, Kansas 67905-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Cobra Oil & Gas Corporation

STATE OF Oklahoma COUNTY OF Woodward, ss.

Glen A. Waugh

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Glen A. Waugh

(Address) P. O. Box 1929, Woodward, OK 73802-1929

SUBSCRIBED AND SWORN TO before me this 5th day of November, 19 92

[Signature]
Notary Public

My Commission Expires: 3-21-96

GEARHART

COMPENSATED DENSITY COMPENSATED NEUTRON LOG

FILING NO. 7563-61 358018	COMPANY <u>COBRA OIL & GAS CORP.</u> WELL <u>EISENBART #1</u> FIELD _____ COUNTY <u>CLARK</u> STATE <u>KANSAS</u> LOCATION: <u>C NE NE SW</u> SEC <u>27</u> TWP <u>34 S</u> RGE <u>35 W</u>
	Other Services <u>DIL/GR</u> <u>SONIC</u>
Permanent Datum <u>GL</u> Elev. <u>1921</u> Log Measured from <u>KB</u> <u>12</u> Ft. Above Perm. Datum Drilling Measured from <u>KB</u>	
Elev.: K.B. <u>1937</u> D.F. <u>1932</u> G.L. <u>1921</u>	
Date	<u>5-26-86</u>
Run No.	<u>ONE</u>
Depth - Driller	<u>5800</u>
Depth-Logger	<u>5797</u>
Bottom logged interval	<u>5795</u>
Top logged interval	<u>2995</u>
Type fluid in hole	<u>CHEM</u>
Density	<u>9.0</u>
Visc.	<u>68</u>
pH	<u>9.0</u>
Fluid Loss	<u>6.4</u>
Max rec. temp., deg F.	<u>127</u> °F
Source of Samples	<u>FLOWLINE</u>
Rm @ Meas. Temp.	<u>1.1</u> @ <u>63</u> °F
Rmf @ Meas. Temp.	<u>.8</u> @ <u>63</u> °F
Rmc @ Meas. Temp.	<u>1.3</u> @ <u>63</u> °F
Source Rmf	<u>M</u>
Source Rmc	<u>M</u>
End Circulation	<u>0300</u>
Logger on Bottom	<u>1054</u>
Recorded By	<u>DEAN</u>
Witnessed By	<u>MR. WAUGH</u>

FIELD
 PRINT
 RECEIVED
 SEP 14 1992
 KANSAS CORPORATION COMMISSION
 CONSERVATION DIVISION
 WICHITA, KS

Run No.	Bore-Hole Record			Casing Record			
	Bit	From	To	Size	Wgt.	From	To
<u>ONE</u>	<u>7 7/8</u>	<u>735</u>	<u>5800</u>	<u>8 5/8</u>	<u>24"</u>	<u>Surf.</u>	<u>735</u>