

STATE OF KANSAS
STATE CORPORATION COMMISSION
260 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-025-20120-0000

LEASE NAME Gabbert Estate

WELL NUMBER 1-24

SPOT LOCATION NE SW SW

SEC. 24 TWP. 34 RGE. 24 (XXX)(W)

COUNTY Clark

Date Well Completed 9/20/76

Plugging Commenced 9/19/84

Plugging Completed 9/26/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Mesa Petroleum Co.

ADDRESS P.O. Box 2009, Amarillo, TX 79189-2009

PHONE # (806) 378-1000 OPERATORS LICENSE NO. 5575

Character of Well Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District I

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation Chester Depth to top 5482' bottom 5496' T.D. 5657'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Chester	Gas	5482'	96'	9-5/8"	1021'	None
				2-7/8"	5657'	3537'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Displaced hole with 9 ppg mud between plugs, pump 20 sxs cement 5617' to 5000'; cut off 2-7/8" csg at 3537' and pulled out to 1100' and pump 70 sxs cement 1100' to 900'; pump 30 sxs cement 500' to 400'; pump 13 sxs cement 40' to ground. Cut off 9-5/8" csg and capped same 3' below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547
Address P.O. Box 506, Liberal, KS 67901

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Texas COUNTY OF Potter, ss.

NOV 01 1984

Richard E. Mathis (employee of operator) xxx

~~xxxxxx~~ of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. E. Mathis

(Address) Mesa Petroleum Co.

SUBSCRIBED AND SWORN TO before me this 30th day of October, 1984

[Signature]
Notary Public

My Commission expires: June 12, 1986

Form CP-4 1-84
Revised 06-83

cc: KCC (0+2), Gen Rcds, Acctg, WF, Liberal, Midland, Partners

WELL LOG

COMPANY MESA PETROLEUM COMPANY

SEC. 24 T. 34S R. 24W

FARM GABBERT ESTATE

NO. 1-24

LOC. 1250' FSL & 1250' FWL


TOTAL DEPTH 5805

COUNTY CLARK, KANSAS

COMM. 7-23-76

COMP. 8-6-76

CONTRACTOR DRILLERS, INC.



CASING

9-5/8" @ 1011'
2-7/8" @ 5650

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0-1020	RED BED
1020-1557	SHALE & LIME
1557-2129	RED BED & SHALE
2129-2310	SHALE
2310-2575	LIME & SHALE
2575-2721	DOLOMITE, LIME, & SHALE
2721-5805	LIME & SHALE

RECEIVED
STATE CORPORATION COMMISSION

JUL 23 1984

CONSERVATION DIVISION
Wichita, Kansas

State of TEXAS
County of HARRIS } SS

I, GARY W. CHAPPELL of HOUSTON, TEXAS

upon oath state the above and foregoing is a true and correct copy of the log of the GABBERT ESTATE#1-24 well.

Subscribed and sworn to before me this 3rd day of September 1976
Gary W. Chappell

My Commission Expires: 6-1-77
Wanda Glover
NOTARY PUBLIC

XC: KGS, Denver Office, file