


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Clark County, Sec. 7 Twp. 34S Rge. (E)24 (W)
Location as "NE/CNW/SW" or footage from lines C SW/4
Lease Owner Mesa Petroleum Co.
Lease Name Klinger Well No. 1-7
Office Address P. O. Box 2009, Amarillo, Tex. 79105
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Sept. 4, 19 75
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced Sept. 4, 19 75
Plugging completed Sept. 4, 19 75
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Clarence Thomas of Garden City)

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 5865
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	870'	8-5/8"	870'	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.


Plugged Hole w/50 sax Cement @ 1000',
35 sax @ 800', 15 sax 40' to 0, 2 sax
in rat hole. Job Completed @ 2:45 A.M.

Name of Plugging Contractor Halliburton
Address R.R. 1, Box 112, Liberal, Kansas 67901

STATE OF KANSAS COUNTY OF SEDGWICK
John R. Bartholomew of Sage Drilling Co., ss.

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John R. Bartholomew
500 Bitting Bldg., Wichita, Kansas
(Address)



Subscribed and sworn to before me this 10th day of September, 19 75.
November 26, 1978.
Louise K. Whitted - Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
SEP 11 1975
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

KLINGER NO. 1-7

CASING RECORD:	OPERATOR: Mesa Petroleum Co.	DESCRIPTION:
8-5/8" set @ 870' w/800 sax cement	CONTRACTOR: Sage Drilling Co.	C SW/4 Sec. 7-34S-24W Clark Co., Kansas
TOTAL DEPTH: 5865'	COMMENCED: August 18, 1975	ELEVATION: 1986KB
	COMPLETED: September 4, 1975	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	119	
Red Bed	119	400	
Red Bed & Sand	400	1200	
Shale	1200	1710	
Shale & Anhydrite	1710	2355	
Anhydrite	2355	2384	
Anhydrite & Shale	2384	2600	
Dolomite	2600	2800	
Anhydrite & Shale	2800	3025	
Shale & Lime	3025	3276	
Lime & Shale	3276	3962	
Shale & Lime	3962	4663	
Lime & Shale	4663	5630	
Shale & Lime	5630	5815	
Lime & Shale	5815	5865	D&A

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RECEIVED
STATE CORPORATION COMMISSION SAGE DRILLING CO., INC.

SEP 11 1975

CONSERVATION DIVISION
Wichita, Kansas

By T. M. McCaul, Jr.
T. M. McCaul, Jr.



Subscribed and sworn to before me this 10th day of September, 1975.

Louise K. Whitted
Louise K. Whitted - Notary Public

My commission expires:
November 26, 1978.