

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15 025-20,747 ²⁰⁸⁴⁴

LEASE NAME Klinger

WELL NUMBER 2-7

SPOT LOCATION 1060 FEL

SEC. 7 TWP. 34 RGE. 24 (XXX) (W)

COUNTY Clark

Date Well Completed 10-27-84

Plugging Commenced 3-8-1988

Plugging Completed 3-14-1988

MAR 16 1988

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kansas Petroleum Inc.

ADDRESS 225 N. Market, Suite 310, Wichita, Ks. 67202

PHONE # (316) 267-2266 OPERATORS LICENSE NO. 5023

Character of Well Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Ks.

Is ACO-1 filled? yes If not, is well log attached? _____

Producing formation Mississippi-Chester Depth to top 5482' bottom 5507' T.D. 5700'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|------------|---------|------|----|--------|--------|------------|
| Surface | | | | 8 5/8" | 845' | 0' |
| Production | | | | 4 1/2" | 5698' | 3065' |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pump 2 sks. hulls & 20 sks. cement to 4900' - Pressured to 1100 lbs. - Mud to 870'

Pump 50 sks. cement 870' to 720' - Mud 720' to 400'

Pump 35 sks. cement 400' to 300' - Mud 300' to 40'

Put bridge & 10 sks. cement 40' to 0'

Cut off 8 5/8" 4' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497
Address Box F, Sublette, Ks. 67877

RECEIVED
STATE CORPORATION COMMISSION

STATE OF KANSAS COUNTY OF HASKELL, ss.

I, Edgar J. Eves

(~~employed by operator~~)

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Edgar J. Eves

(Address) Box F, Sublette, Ks.

SUBSCRIBED AND SWORN TO before me this 16th day of March, 19 88

Sondra L. Eves
Notary Public

My Commission expires: 12-6-88



15-025-20844-0000

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH McCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE

November 30, 1987

FEB 30 '88

WELL PLUGGING NOTICE

EXPIRES

Klinger #2-7
3870' FSL 1060' FEL
Sec. 07-34S-24W
Clark County

Kansas Petroleum, Inc.
225 N. Market, Ste. 310
Wichita, KS 67202

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist
Director
State Corporation Commission

DISTRICT #1 302 W. McArtor, Dodge City, KS 67801 (316) 225-6760