

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20,896-0000

LEASE NAME Mehl "A"

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1980 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 26 TWP. 34S RGE. 34 (W)

COUNTY Seward

Date Well Completed 1/25/86

Plugging Commenced 1/26/86

Plugging Completed 1/26/86

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS Box 351, Liberal, Kansas 67901

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 6725

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8	1627	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

50 sxs cmt @ 6725, 100 sxs @ 3800, 50 sxs 1627, 40 sxs 800, 10 sxs 40-0, 15 sxs in rathole, 10 sxs in mousehole, heavy drilling mud placed between each plug. Complete 1400 hrs 1/26/86.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor _____ License No. _____


Address _____

STATE OF Kansas COUNTY OF Seward, ss.

Paul Campbell (Employee of Operator) or ~~operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Paul Campbell
Paul Campbell, Division Production Manager
(Address) Box 351, Liberal, Kansas 67901

SUBSCRIBED AND SWORN TO before me this 14th day of February, 19 86



Elizabeth J. Hooper
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
1/26/86

FEB 18 1986

CONSERVATION DIVISION
Wichita, Kansas

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

MEHL A #1
1,980' FSL & 1,650' FWL Section 26-34S-34W
Seward County, Kansas

Commenced: 1-9-86

Completed: 1-26-86

OPERATOR: ANADARKO PRODUCTION COMPANY

Rig 12


From	Depth	To	Formation	Remarks
0		30	Cased hole	30' of 20" csg.
30		1,020	Sand-Redbed	
1,020		1,530	Redbed-Sand	Ran 38 jts. of 24# 8 5/8"
1,530		1,630	Redbed-Anhy	csg. LD @ 1,627' w/ 600 sks.
1,630		6,512	Lime-Shale	50/50 Posmix 2% CC 200 sks.
6,512		6,570	Core #1	Common 2% CC PD @ 12:30 P.M.
6,570		6,628	Core #2	1-10-86
6,628		6,725	Lime-Shale	1" to 60' w/ 200 sks. Common Complete @ 5:45 P.M. 1-10-86

6,725 - TD


D & A

State of Kansas) I, the undersigned, being duly sworn on oath, state
County of Sedgwick) that the above Drillers' Well Log is true and correct
) to the best of my knowledge and belief and according
) to the records of this office.

GABBERT-JONES, INC.


James S. Sutton, II -- President

Subscribed & sworn to before me this
4th day of February, 1986.


Lola Lenore Costa

My Commission expires November 21, 1988.

RECEIVED
STATE CORPORATION COMMISSION
FEB 18 1986
CONSERVATION DIVISION
Wichita, Kansas