

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Seward SEC. 12 TWP. 34S RGE. 31W E/W (1)
Location as in quarters or footage from lines:
C NW SW

Lease Owner Inca Oil Co.
Lease Name Hilbig Well No. 1
Office Address Box 1869 Liberal, Kansas 67901
Character of Well (Completed as Oil, Gas or Dry Hole): Dry
Date Well Completed 12-15-79 Recompleted 1-20-84
Application for plugging filed 1-23-84
Plugging commenced 9-18-84
Plugging completed 9-20-84
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi

Producing formation _____ Depth to top _____ bottom T.D. 6117

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	1508	none
				4 1/2	6116	2726

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pump 35 sks. of cement @ 5808 to 5320

Pump 40 sks. of cement @ 1560 to 1460

Pump 30 sks. of cement @ 700 to 600

Put 10 sks. of cement @ 40 to 0

Cut off & cap 8 5/8 3' below ground level

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling Ser. Box 506 Liberal, Kansas 67901

STATE OF Kansas COUNTY OF Seward, ss.

Roger D. Brown (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Roger D. Brown

(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of October, 1984

Brenda L. King
Notary Public.

My Commission expires _____



RECEIVED
STATE CORPORATION COMMISSION

OCT 15 1984

THE WIL-MC CORP. #1 HILBIG 12-34-31W
 607 FIDELITY UNION LIFE BLDG, DALLAS, TX. C NW SW
 CONTR ZENITH DRILLING CORP. CTY SEWARD

GEOL _____ FIELD IRIS EXT _____
 # 2687 KR. CM/21/74 CARD ISSUED 5/23/74 IP D&A/MISS

+	+
+	+

NO. 15-175-20,223

LOG TOPS	DEPTH	DATUM
KRI	2824	+ 63
WIMP	2716	- 29
ET RI	2786	- 99
BKLF	2964	- 277
CO GR	2984	- 297
CO GR PAY	3127	- 440
SLVA	4078	-1391
BEED	4308	-1621
LJR	4328	-1641
LANS	4445	-1759
BRUM	4721	-2034
HODGES	4984	-2267
MARI	5100	-2414
CHEK	5295	-2608
MEY SH	5608	-2921
MEY SD	5688	-3001

16" 65; 8-5/8" 1508/8508X
 DST (1) (NRW SD) 5655-5704/34', 60'
 DM (NS) NO SIP, TOOL FAILED, FP
 57-
 DST (2) 5790-5811/30-60-60-60, 50' M W/
 50, BHP 51-103#, FP 50-50#, 50-50#
 DST (3) (CO GR) 3098-3156 (H-W)/30-60-
 60-60, 135' SGCM, 90' WM, 180' MW,
 BHP 734-596#, FP 92-138#, 161-
 229

ADDITIONAL LOG TOPS:

MISS CHEST	5790	-3103
STE GEN	5842	-3155
ST LOUIS	5970	-3283
RTD	6120	-3433
LTD	6121	-3434

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

RECEIVED
 STATE CORPORATION COMMISSION

SEP 18 1984

CONSERVATION DIVISION
 Wichita, Kansas