

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-025-21,036-0000

LEASE NAME Bertha M. Gabbert Trust

WELL NUMBER #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4620 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 35 TWP. 34 RGE. 24W (E) or (W)

COUNTY Clark

LEASE OPERATOR Jay Boy Oil, Inc.

ADDRESS 224 E. Douglas, #425

PHONE# (316) 264-3700 OPERATORS LICENSE NO. 4569

Date Well Completed 12/13/89

Character of Well Lost hole P&A

Plugging Commenced 11/29/90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11/29/90

The plugging proposal was approved on _____ (date)

by _____ (KCC District Agent's Name).

Is AC0-1 filed? no If not, is well log attached? no log run

Producing Formation none Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
surface		0	120	13 3/8	120	0
surface		120	680	8 5/8	680	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

See attached

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Patrick Well Service License No. 7547

Address 852 Petroleum Rd. Liberal, Kansas 67901

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Jay Boy Oil, Inc.

MAR 13 1991

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Kenneth R. Greenwood, Exploration Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Kenneth R. Greenwood

(Address) 224 E. Douglas #425 Wichita, Ks.

SUBSCRIBED AND SWORN TO before me this 13th day of March, 19 91

Betty B. Herring Betty B. Herring
Notary Public

BETTY B. HERRING
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 10-07-93

Commission Expires: 10-07-93

15-025-21036

Sabbert Trust #1

11/29/90 Dig out cellar to 13 3/8" conductor pipe. Found conductor 8' below GL. Patrick Well Service-MIRU. Ran Homco 1 1/4" drill pipe, using Homco slips and elevators, down annulus between surface and conductor pipe. In soft drilling mud at 90'. Pull drill pipe. Ran down 8 5/8" to 615'. RU Hal. Circ. 60/40 Posmix with 6% gel to surface. 183 sx total. Pull drill pipe. Ran down backside. Circ. to 110'. Hit cement. Circ. cement to surface with 43 sx. Pull drill pipe. Rig down. Job complete at 5:00 P.M.

RECEIVED
STATE CORPORATION COMMISSION

MAR 13 1991

CONSERVATION DIVISION
Wichita, Kansas