

RECEIVED

SEP 10 2003

KCC WICHITA

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API # 1512921567 ~~2001~~ (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549  
(owner/company name) (operator's)

ADDRESS 1201 Lake Robbins Drive CITY The Woodlands

STATE Texas ZIP CODE 77380 CONTACT PHONE (832) 636-3899

LEASE KU ENDOWMENT WELL# G-1 SEC. 21 T. 33S R. 39 (xxxx/West)

NW - SW - SW - NW SPOT LOCATION/QQQQ COUNTY MORTON

3180' FEET (in exact footage) FROM X/S (circle one) LINE OF SECTION (NOT Lease Line)

4950' FEET (in exact footage) FROM X/E (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET#

CONDUCTOR CASING SIZE  SET AT  CEMENTED WITH  SACKS

SURFACE CASING SIZE 8-5/8 SET AT 1706' CEMENTED WITH 435' SACKS

PRODUCTION CASING SIZE 5-1/2 SET AT 4699' CEMENTED WITH 90 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: CIBP @ 4300'. PERFS: 3200'-3218' & 4518'-4530'

ELEVATION 3240' / XXXXX T.D. 6532' PBDT 4648' ANHYDRITE DEPTH  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING SET CIBP@ 3150'. DUMP 2 SXS CMT ON CIBP. SHOOT OFF 5-1/2 CSG @ +/- 1800. SPOT 50 SXS CMT FROM 1775' TO 1625'. SPOT 40 SXS CMT FROM 700 TO 580. SPOT 15 SXS CMT FROM 40 TO 4. CUT OFF AND CAP 8-5/8 CSG 4 BELOW GL.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? LOGS SUBMITTED W/ ORIG. COMPLETION REPORT OR DRILLER'S LOG.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

DAWN NEASE PHONE# (620) 544-6200

ADDRESS PO BOX 40 City/State HUGOTON, KS 67951

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151  
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL 9-5-03 Plugged

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 9-4-03 AUTHORIZED OPERATOR/AGENT: Craig R. Walters

CRAIG R. WALTERS, P.E. (Signature)  
ENGINEERING SUPERVISOR

8/03

1/04