

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

**WELL PLUGGING APPLICATION FORM**  
(File One Copy)

API NUMBER 15-025-20,951-0000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Cobra Oil & Gas Corporation OPERATOR'S LICENSE NO. 8802 7-93

ADDRESS P. O. Box 1929, Woodward, OK 73802-1929 PHONE # (405) 254-2027

LEASE (FARM) Isenbart 27 WELL NO. 1 WELL LOCATION C-NE-NE-SW COUNTY Clark

SEC. 27 TWP. 34S RGE. 24 (E) or (W) (W) TOTAL DEPTH 5800' PLUG BACK TD 5768'

**Check One:**

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8" SET AT 735' CEMENTED WITH 150 sx. Reg. SACKS

CASING SIZE 4 1/2" SET AT 5799' CEMENTED WITH 250 sx. Reg. SACKS

PERFORATED AT 5566' - 73' & 5575' - 90'

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set 4 1/2" C.I.B.P. @ 5380' & dump bailed 2 sx. cmt., shoot

4 1/2" csg. off & lay down to 1000', pump 40 sx. cmt. plug @ 1000', pull csg. to 760', pump 50  
sx. cmt. plug @ 760', pull csg. to 40', pump 10 sx. cmt. plug @ 40' up to 4', cut csg. off  
4' below ground level & weld on plate.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes  
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN As soon as possible.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE  
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Glen A. Waugh PHONE # (405) 254-2027

ADDRESS P. O. Box 1929, Woodward, OK 73802-1929

PLUGGING CONTRACTOR Sargent's Casing Pulling LICENSE NO. ~~8-269~~ 6547 6-93

ADDRESS P. O. Box 596 Liberal, Kansas 67905 PHONE # (316) 624-7455

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Glen A. Waugh by Paul Powers  
(Operator or Agent)

DATE: SEPTEMBER 11, 1992

Joan Finney  
Governor

Jim Robinson  
Chairman

F. S. Jack Alexander  
Commissioner

Rachel C. Lipman  
Commissioner

Judith McConnell  
Executive Director

Brian Moline  
General Counsel



# Kansas Corporation Commission

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

September 15, 1992

Cobra Oil & Gas Corp  
Box 1929  
Woodward OK 73802-1929

Isenbart 27 1  
API 15-025-20,951  
C NE NE SW  
Sec. 27-34-24W  
Clark County

Dear Operator:


This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000. If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

  
David P. Williams  
Production Supervisor

Conservation Division  
William R. Bryson  
Director  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, Kansas 67202-1286  
Telephone (316) 263-3238

District: #1 304 W. McArtor  
Dodge City, KS 67801  
(316) 225-6760