

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-025-²⁰⁸⁴⁴⁻⁰⁰⁰⁰20,747 (of this well) 6/88
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Kansas Petroleum, Inc. OPERATORS LICENSE NO. 5023
ADDRESS 225 N. Market, Suite 310; Wichita, KS 67202 PHONE # (316) 267-2266
LEASE (FARM) Klinger WELL NO. 2-7 WELL LOCATION 1060 FEL 3870' FSL COUNTY Clark
SEC. 7 TWP. 34S RGE. 24 (X) or (W) TOTAL DEPTH 5700' PLUG BACK TD 5641'

Check One:

OIL WELL _____ GAS WELL X D & A _____ SWD or INJ WELL _____ DOCKET NO. _____
SURFACE CASING SIZE 8-5/8" SET AT 845' CEMENTED WITH 450 SACKS
CASING SIZE 4-1/2" SET AT 5698' CEMENTED WITH 150 SACKS
PERFORATED AT 5482 - 5487; 5502 - 5507

1410
3770
5180

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Pump 50 sx cement across perfs - shoot off casing - pump cement plug out bottom of casing - reclaim casing to bottom of 8-5/8" casing - pump plug across bottom of 8-5/8" casing - finish reclaiming casing. Put 10 sx cement in top of 8-5/8" casing - cut off 8-5/8" 3' below ground level.
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Prev. Submitted IS ACO-1 FILED? Yes
(If not, explain)

RECEIVED
STATE CORPORATION COMMISSION

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NOV 7 6 48 AM
CONSERVATION DIVISION
Wichita, Kansas

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Terry W. Maxwell PHONE # (316) 624-3767
ADDRESS Box 2587; Liberal, KS 67905-2587

PLUGGING CONTRACTOR Midwest Casing Pullers LICENSE NO. 6497

ADDRESS Box F; Sublette, KS 67877 PHONE # (316) 675-8349

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Terry Maxwell
(XXXXXXXXXX Agent)

DATE: 11-24-87

1