

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-019-24,529-

LEASE NAME Burkett

WELL NUMBER 1 Rig-uall

SPOT LOCATION SE SW SE

SEC. 8 TWP. 34 SRGE. 10 E.

COUNTY Chautauqua

Date Well Completed 6/6/1984

Plugging Commenced 6/6/1984

Plugging Completed 6/6/1984

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR O-Petro Energy Corp.

ADDRESS P.O. Box 116, Sedan, Kansas 67361

PHONE # (316) 725-3721 OPERATORS LICENSE NO. 7625

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Chanute, Kansas 66720

Is ACO-1 filed? Yes If not, is well log attached? (a)

Producing formation Dry hole Depth to top --- bottom --- T.D. 1900

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		surface	40	7 5/8"	40	cemented pipe
DRY HOLE						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. 1) Condition hole with gel

- 2) Cemented from TD up 50' with 12 sacks of cement with 4% gel (1900' - 1850')
- 3) Cement from 700' up 50' with 12 sacks of cement with 4% gel (700' - 650')
- 4) Cement from 350' to surface with 80 sacks cement with 4% gel (350' - surface)
- 5) Restore surface to as near original condition as possible

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Darnall Drilling License No. 6282

Address South of City, Sedan, Kansas 67361

STATE OF KANSAS COUNTY OF CHAUTAUQUA, ss.

Thomas H. Oast (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.


RECEIVED
STATE CORPORATION COMMISSION

(Signature) Thomas H. Oast
(Address) P.O. Box 116
Sedan, KANSAS 67361

JUN 29 1984

SUBSCRIBED AND SWORN TO before me this 27 day of June, 1984

CONSERVATION DIVISION
Wichita, Kansas
My Commission expires:



Phyllis A. McNown
Notary Public