

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

7-13-84

API NUMBER 15-019-24,473-0000

LEASE NAME Burkett

WELL NUMBER #1 Myson

SPOT LOCATION C-SW-SW-SE-SE

SEC. 8 TWP. 34 RGE. 10 (E) or (W)

COUNTY Chautauqua

Date Well Completed June 6, 1984

Plugging Commenced June 6, 1984

Plugging Completed June 6, 1984

LEASE OPERATOR Myson Resources Inc.

ADDRESS 1230 First Oklahoma Tower Okla City, Ok 73102

PHONE # (316) 725-3721 OPERATORS LICENSE NO. 9279

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Chanute, Kansas 66720

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing formation DRY HOLE Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 1890'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		Surface	42'	7"	42'	Cemented pipe
DRY HOLE						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. 1) Condition hole with gel

- 2) Cemented from TD up 50' with 12 sacks of cement with 4% gel (1890'-1840')
- 3) Cement from 700' up 50' with 12 sacks of cement with 4% gel (700' - 650')
- 4) Cement from 350' to surface with 80 sacks cement with 4% gel (350' - surface)
- 5) Restore surface too as near original condition as possible

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Darnall Drilling License No. 6282  
Address South of City, Sedan, Kansas 67361

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF KANSAS COUNTY OF CHAUTAUQUA, ss.

JUL 11 1984

Thomas H. Oast (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Thomas H. Oast

(Address) P.O. Box 116  
Sedan, Kansas 67361

SUBSCRIBED AND SWORN TO before me this 26 day of June, 1984

NOTARY PUBLIC - State of Kansas  
PHYLLIS A. MCNOWN  
My Appt. Exp. 6-10-85

Phyllis A. McNown  
Notary Public

My Commission expires: