

STATE OF KANSAS
STATE CORPORATION COMMISSION


15-077-20425-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Harper County, Sec. 15 Twp. 34 Rge. 6W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NE NE SW

Lease Owner Worsham Consultants, Inc.
Lease Name Wilcox Well No. 3
Office Address 1405 Federal Boulevard, Denver, CO 80204
Character of Well (Completed as Oil, Gas or Dry Hole) Dry hole



Locate well correctly on above
Section Plot

Date Well completed June 10, 1977
Application for plugging filed June 10, 1977
Application for plugging approved June 10, 1977
Plugging commenced June 10, 1977
Plugging completed June 10, 1977
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well J. W. Metz
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3890'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	260'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 260', 35 sacks cement
Mud to 40', plug, 1/2 sack hulls and 12 sacks cement
5 sacks cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1977
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Don Gardner (employee of owner) ~~owner~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Suite 250, ~~200~~ W. Douglas, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of June, 1977

Kathleen L. Durbin
Notary Public.

My commission expires January 4, 1981

DRILLERS LOG

#3 WILCOX
 NE NE SW Section 15-34-6W
 Harper County, Kansas

OPERATOR: WORSHAM CONSULTANTS, INC.
 1405 Federal Boulevard
 Denver, Colorado 80204

CONTRACTOR: DUNNE-GARDNER PETROLEUM, INC.
 Suite 250, 200 West Douglas
 Wichita, Kansas 67202

COMMENCED: June 2, 1977

COMPLETED: June 10, 1977

CASING RECORD: 8-5/8" @ 260' w/225 sx

<u>FROM</u>	<u>TO</u>	<u>DESCRIPTION</u>
0	265	Clay - shells
265	580	Blue-gray shale
580	3630	Lime and shale
3630	3735	Lime
3735	3830	Lime and shale
3830	3890	Lime
3890		Rotary total depth

RECEIVED
 GAME COMMISSION COMMISSION
 JUN 21 1977
 CONSERVATION DIVISION
 Wichita, Kansas


STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct log to the best of my knowledge and belief.


 Don Gardner

Subscribed and sworn to before me this 15th day of June, 1977.

My appointment expires:
 January 4, 1981


 Kathleen L. Durbin
 Notary Public