

STATE OF KANSAS
STATE CORPORATION COMMISSION
D. S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

077

API NUMBER 15-007-21,211-0001

LEASE NAME Harmon

WELL NUMBER 17-A

4950 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 17 TWP. 34 RGE. 7W (E) or (W)

COUNTY Harper

Date Well Completed _____

Plugging Commenced 9-2-97

Plugging Completed 9-8-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Phillips Exploration Company

ADDRESS 2338 Bromfield Circle Wichita, Kansas 67226

PHONE# (316) 687-9983 OPERATORS LICENSE NO. 31160

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Steve Vangesen (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 5127'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	237'	None
				5-1/2"	5127'	3818'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each section. Plugged off bottom with sand to 4750' and 5 sacks cement. Shot pipe @ 4016', 3818', layed down 58' its. Well casing, pumped 20 bbls. water, didn't kill, pumped 45 bbls. mud down 5-1/2" pulled 3' its. pumped 50 sks. cement. Pulled rest of 5-1/2", ran tubing to 1700', pumped 45 sks. gel to kill well, pulled to 1309', pumped 50 sks. cement, pulled tubing out, pulled to 905', pumped 35 sks. cement, pulled to 312' and circulated cement to surface. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Phillips Exploration Co. L.C.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 16th day of September, 19 97

Irene Herzberg
Notary Public

My Commission Expires: _____

