


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely.  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Harper County, Sec. 2 Twp. 34 Rge. 8 E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
C of SW/4  
Lease Owner Cities Service Oil Co.  
Lease Name Jacobs A#1 Well No. \_\_\_\_\_  
Office Address Russell, Kansas 67665  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Locate well correctly on above  
Section Plot

Date Well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 3/3/78 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 3/13/78 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_  
\_\_\_\_\_ depleted.  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owens  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4681  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	359	none
				5 1/2"	4680	3928'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded from 4668 to 4600' and ran 5 sacks cement. Shot pipe at 4022', 3902', pulled 122 joints. Squeezed hole with 3 sacks hulls, 15 sacks gel. Released plug and displaced with 125 sacks common cement with 2% gel, 3% cc. (Mud from 4560 to 415', 3 sacks hulls from 415 to 400' and 125 cement from 400' to base of cellar.)

PLUGGING COMPLETE

RECEIVED  
STATE CORPORATION COMMISSION

MAR 17 1978

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor KELSO CASING PULLING  
CHASE, KANSAS

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.  
R. DARRELL KELSO (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of March, 1978



Margaret Melcher  
Notary Public.

My commission expires \_\_\_\_\_

DRILLERS LOGJACOBS "A" NO. 1

CASING RECORD:	OPERATOR:	Cities Service Oil Co.	DESCRIPTION:
8-5/8" @ 358' w/250 sax cement	CONTRACTOR:	Sage Drilling Co., Inc.	C SW Sec. 2-34S-8W Harper County, Kansas.
TOTAL DEPTH:	COMMENCED:	June 4, 1973	
4680'	COMPLETED:	June 17, 1973	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Shale	0	360	
Shale	360	930	
Shale, Shells & Red Bed	930	1590	
Lime & Shale	1590	3555	
Shale & Lime	3555	3675	
Lime & Sand	3675	3725	
Lime & Shale	3725	3925	
Shale	3925	4200	
Lime & Shale	4200	4300	
Lime	4300	4533	
Shale & Sand	4533	4600	
Shale & Lime	4600	4658	
Lime	4658	4680	5½" @ 4680' w/150 sax cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 03 1978

CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Clarence Michael  
Clarence Michael

Subscribed and sworn to before me this 18th day of June 1973.



Louise K. Whitted  
Louise K. Whitted, Notary Public

My commission expires:  
November 26, 1974.