

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-077-20,213-0000

LEASE NAME Wharton Gas Unit

WELL NUMBER 1-2

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

4620 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 2 TWP. 34 SRGE. 8 or W

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 110 S. Main, Suite 500, Wichita, KS 67202 COUNTY Harper

PHONE# (316) 265-9697 OPERATORS LICENSE NO. 5003 Date Well Completed 11-23-73

Character of Well _____ Plugging Commenced 2-21-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging Completed 2-21-91

The plugging proposal was approved on 2-21-91 (date)

by Steve Van Gieson (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Mississippian Depth to Top _____ Bottom _____ T.O. 4676'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | 0 | 8-5/8" | 280' | 0 |
| | | | 0 | 4-1/2" | 4652' | 3500 |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Set CIBP 4640' capped with 2 sacks cement. Shoot casing according to stretch. Pull casing to 1351' & spot 35 sacks of cement. Pull casing to 884' & spot 35 sacks of cement. Pull casing to 353' & circulate cement to surface. Pull remaining casing from wellbore & top off cement. Well complete 2-21-91.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hayes Well Service License No. 5429

Address Attica, Kansas


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

McCoy Petroleum Corporation (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 110 S. Main, Suite 500
Wichita, KS 67202



before me this 28th day of February, 19 91
Deborah Ann Paulus
 Notary Public