

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market - Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-21964-0000

LEASE NAME Wheeler

WELL NUMBER 1-2

3907 Ft. from S Section Line

1267 Ft. from E Section Line

SEC. 1 TWP. 34S RGE. 35W (E) or (W)

COUNTY Stevens

Date Well Completed 10/7/95

Plugging Commenced 5/16/01

Plugging Completed 5/22/01

LEASE OPERATOR Texaco E&P, Inc.

ADDRESS 1109 Skelly Ave. Guymon, OK 73942

PHONE # 580 338-6820 OPERATORS LICENSE NO. 4742

Character of Well Gas

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5/15/01 (date)

by Steve Middleton (KCC District Agent's Name)

is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Chase Depth to Top 2656 Bottom 2792 T.D. 2900 PBTD 2859

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Chase	Gas	2656	2792	8 5/8"	641	-0-
				4 1/2"	2899	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set

See Attached Daily Report

Name of Plugging Contractor H&K Plugging & Salvage License No. 31705

Address P.O. Box 2742 Pampa, TX 79066-2742

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Texaco E&P, Inc. / Ken Austin

STATE OF Oklahoma COUNTY OF Texas, ss.

Texaco E&P Inc. / Ken Austin (Employee of Operator) or (Operator) of above-described

well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 1109 Skelly Ave. Guymon, OK 73942

SUBSCRIBED AND SWORN TO before me this 29th day of May, 2001

H. Dean Diehl Notary Public
My Commission Expires: 4/3/04

RECEIVED
KANSAS CORPORATION COMMISSION

USE ONLY ONE SIDE OF EACH FORM

JUN 1 2001 Form CP-4
KCC 05-88

CONSERVATION DIVISION

OR

Holman Services

Well Plugging Specialist

Phone 806-665-2550 * Fax 806-665-2719
 P. O. Box 2742 Pampa, Texas 79066-2742
 Dennis Lee Holman

Texaco E&P, Inc
 Daily P&A Report
 Wheeler 1-2

5-16-01

Moved in, rigged up P&A rig, rods stuck, backed off 65 rods and layed down, shut down for night

5-17-01

Strip out rod and tubing, pumped 40 barrels 9.5# mud, ran gauge ring to 2606 feet, ran and set CIBP at 2590 feet with 2 sacks cement on top, tested between 8 5/8 and 4 1/2 to 300# tested okay, ran tubing to 1600 feet, circulated hole with 9.5# mud, pumped 30 sacks cement pulled tubing to 672 feet, pumped 30 sacks cement, pulled tubing to 60 feet, pumped 10 sacks cement to surface, rigged down, shut down for night *Kevin Stepe/KCC*

5-18-01

Rained out, rig on location on Wheeler 1-2

5-21-01

Rained out, rig on location Wheeler 1-2

*CIBP @ 2590
 2 sx cunt. 9.5# mud
 to 1600' - spot 30 sx cunt.
 9.5# mud to 672' spot 30 sx
 cunt.
 @ 60' 10 sx cunt. to surface.*

RECEIVED
 KANSAS CORPORATION COMMISSION

JUN 1 2001

CONSERVATION DIVISION

Holman Services

Well Plugging Specialist

Phone 806-665-2550 * Fax 806-665-2719

P. O. Box 2742 Pampa, Texas 79066-2742

Dennis Lee Holman

Texaco E&P, Inc
Wheeler & Rittenour

5-22-01

Dug out and cut off casing head, welded on steel ID plate

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 1 2001

CONSERVATION DIVISION



Texaco North America Production
1109 Skelly Ave.
Guymon, OK 73942
580 338 6820

May 29, 2001

Kansas Corporation Commission
Conservation Division
130 South Market, RM 2078
Wichita, KS 67202

RE: Wheeler #1-2
API # 15-189-21964
C / NE Sec. 1 T34S R35W
Stevens County Kansas

Gentlemen:

Attached is a Form CP-4 Well Plugging Record, for the subject well.

If you need anything more give me a call @ 580-338-6820.

Thanks,

H. Dean Dreher

Attachments

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 1 2001

CONSERVATION DIVISION