

15-175-10/51-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
130 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER NA (SPUD 5/25/63)

LEASE NAME POTTROFF "A"

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

4030 Ft. from S Section Line

1390 Ft. from E Section Line

SEC. 34 TWP. 34S RGE 34 (E) or (W)

COUNTY SEWARD

Date Well Completed 6/14/63

Plugging Commenced 2/25/97

Plugging Completed 2/28/97

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2/20/97 (date)

by MR. GARY WINTERS (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation CHASE Depth to Top 2614' Bottom 2626' T.D. 2740'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
CHASE	GAS	2614'	2626'	8-5/8"	790'	3'
				4-1/2"	2739'	1245'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. MIRU SARGENT & HORTON CP. PMPD 2 SXS HULLS + 20 SXS CMT FROM 2614'-2414'. PULL FREE PT & CUT OFF 4-1/2" CSG @ 1803' & PULLED TO 1775'. PMPD 40 SXS CMT FROM 1775'-1675'. STUCK PIPE. SHOT LOOSE @ 1230'. PULLED CSG TO 820'. PMPD 40 SXS CMT FROM 820'-720'. PULLED CSG TO 40'. PMPD 10 SXS CMT FROM 40'-0'. CUT OFF & CAPPED 8-5/8" CSG 3' BELOW GL. REC 39 JTS OF 4-1/2" 9.5# CSG (1245').
KCC WITNESS: GARY WINTERS

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 498A, TYRONE, OK 73951-9731 PHONE: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John A. Broman

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 5th day of March, 1997

FREDA L. HINZ
Notary Public - State of Kansas
My Appt. Expires 5-15-99

My Commission Expires: _____

RECEIVED
KANSAS CORP COM
1997 MAR -6 P 1:33