


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Seward County, Sec. 32 Twp. 34 Rge. 34 N/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
C NW NW SW NE
Lease Owner Tucker Production Corporation
Lease Name ENGEL Well No. #1
Office Address 2546 W. Main Littleton, Colorado 80120
Character of Well (Completed as Oil, Gas or Dry Hole)
DRY HOLE
Date Well completed September 3 1981
Application for plugging filed September 8 1981
Application for plugging approved 19
Plugging commenced September 3, 1981
Plugging completed September 3, 1981
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plot

If a producing well is abandoned, date of last production
N/A 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas, Jr.
Producing formation -- Depth to top -- Bottom --- Total Depth of Well 6740'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		Conductor	Pipe	57 $\frac{1}{2}$ '	65'	none
		Surface	CSG.	8-5/8"	1774.22'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged well with 50 sacks/ 1700-rubber plug
10 sacks plug 0-40'
5 sacks in rat hole
5 sacks in mouse hole
Completed at 8:30 a.m. September 3, 1981

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

RECEIVED
STATE CORPORATION COMMISSION
SEP 14 1981

STATE OF Kansas COUNTY OF Seward
Elmer Jack Taylor (employee of owner) or (owner/operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Elmer Jack Taylor
P.O. Box 1157 Liberal, Kansas 67901
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of September, 1981

Marnell Pribble
Notary Public.

My commission expires August 3, 1983



DRILLERS LOG

TUCKER PRODUCTION CORPORATION
2546 W. Main
Littleton, Colorado 80120

TOTAL DEPTH: 6740

Engel #1
C-NW NW SW NE of Sec.32-34-34W
Seward County, Kansas

SURFACE CASING: Drilled 1774'
of 12 1/4" hole. Ran 46 joints new
23# 8-5/8" surface casing 1774.22'
OA, set @ 1753' KB. Cemented with
700 sks. lite, 2% CC, 1/4# flocele,
150 sks. class H, 3%CC. Plug down
@ 8:30 a.m. 9/3/81. Plug held,
cement circulated.

Commenced: August 21, 1981
Completed: September 3, 1981


FORMATION	FROM	TO	REMARKS
Surface sand, lime	0'	817'	RTD 6740'
Red bed	817	818	
Lime	818	1424	LTD 6731'
Red bed	1424	1754	
Lime	1754	2476	
Lime, shale	2476	6740	
RTD		6740	

I certify that this is a true and correct copy of the log on the above captioned well to the best of my knowledge.

NRG Drilling, Inc.

By Elmer Jack Taylor
Elmer Jack Taylor

Subscribed and sworn before me this 8th day of September, 19 81



Marrnell Pribble
Notary Public
Marrnell Pribble
RECEIVED
STATE CORPORATION COMMISSION

My commission expires: 8-3-83

SEP 14 1981
CONSERVATION DIVISION
Wichita Kansas