

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-189-20855-0000

LEASE NAME Skinner "C"

WELL NUMBER 2

1980 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 15 TWP. 34S RGE. 35 ~~W~~ W

COUNTY Stevens

Date Well Completed 8/1/85

Plugging Commenced 6/12/86

Plugging Completed 7/15/86

LEASE OPERATOR Cities Service Oil and Gas Corporation

ADDRESS 3545 NW 58th Street, Oklahoma City, OK 73112

PHONE#(405) 949-4432 OPERATORS LICENSE NO. 5447

Character of Well gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District Office #2

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation Morrow Depth to Top 6158 Bottom 6194 T.D. 6750' KB

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	dry	6158	6194	13-3/8"	749'	
				8-5/8"	1714'	
				5-1/2"	6747'	2796'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.

RIH w/5.5" OD Arrow CIBP to 6000' KB. Set CIBP. Dumped 2 sx cmt on top of plug. Cut off 5.5" csg at 2797'. Established circ. w/115 bbls mud. Set 40 sx Class H cmt plug at 2797'. POH w/5.5" csg to 1765. Established circ. at 1765' w/drilling mud. Set 50 sx plug at 1765'. Pulled 5.5" csg to 807. Set 50 sx Cl. H cmt plug at 807'. Pulled csg to 40' & set 10

(If additional description is necessary, use BACK of this form.)  
 sx Cl. H cmt plug. Cut off 8-5/8" csg flange. Welded on plate. Well P & A on 7/15/86.

Name of Plugging Contractor DACO, Inc. License No. \_\_\_\_\_

Address Drawer 3010, Borger, Texas 79008

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Del G. Oliver, Engineering Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Del G. Oliver

(Address) 3545 NW 58th Street  
 Oklahoma City, Oklahoma 73112

SUBSCRIBED AND SWORN TO before me this 24<sup>th</sup> day of July, 1986

Debra G. Howeth  
 Notary Public

My Commission Expires: 4-24-89

JUL 29 1986

Form CP-  
 Revised 08-2