

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-20,337-0002

LEASE NAME GASKILL "A"

130 South Market, Rm 2078
Wichita, Kansas 67202

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

WELL NUMBER 2

1320' Ft. from S Section Line

1470' Ft. from E Section Line

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

SEC. 10 TWP. 33S RGE 38 (E) or (W)

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

COUNTY STEVENS

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 04/09/77

Character of Well GAS

Plugging Commenced 11/02/97

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11/02/97

The plugging proposal was approved on 10/29/97 (date)

by MR. STEVE DURANT (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached?

Producing Formation CHEROKEE Depth to Top 5190' Bottom 5198' T.D. 6520'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
CHEROKEE	GASS	5190'	5198'	8-5/8"	1697'	4'
				4-1/2"	6216'	2650'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. MIRU CSG PULLERS, PMPD 2 SXS HULLS & 20 SXS CMT TO PLUG 5190-4990. CUT OFF 4-1/2" CSG @ 2650. PULL CSG TO 2600, PMPD 35 SXS CMT TO PLUG 2600-2500. PULL CSG TO 1710, PMPD 50 SXS CMT TO PLUG 1710-1560. PULL CSG TO 600, PMPD 40 SXS CMT TO PLUG 600-500. PULL CSG TO 40', PMPD 10 SXS CMT TO PLUG 40-0'. CUT OFF 8-5/8" CSG & CAP 4' BELOW GL. CONTACTED STEVE DURANT.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, SS.

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God

(Signature) JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 8th day of December, 1997

Shirley J. Childers
Notary Public

My Commission Expires: 11/14/98

