

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
130 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-21926 - 0000

LEASE NAME DEMUTH "B"

WELL NUMBER 3

3910 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 22 TWP. 33 RGE. 39 (X) or (W)

COUNTY STEVENS

Date Well Completed 6-13-95

Plugging Commenced 9-17-95

Plugging Completed 9-18-95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-16-95 (date)

by STEVE MIDDLETON (KCC District Agent's Name)

Is AC0-1 filed? YES (8/95) If not, is well log attached? _____

Producing Formation NONE Depth to Top _____ Bottom _____ T.D. 6248

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 1699' | NONE |
| | | | | 5-1/2" | 3469' | 1900' |
| | | | | | | |
| | | | | | | |

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

MIRU CSG PULLERS, PUMPED 2SX HULLS & 10 SX CMT FROM 3053-3103 FT. DISP W/72 BBL MUD. PULL FREE POINT & CUT OFF 5-1/2" @ 1900 FT. SPOT 35 SX CMT FROM 1900 TO 1750 FT. TOH TO 1730 FT & SPOT 50 SX FROM 1730 TO 1580 FT. TOH TO 600 FT & SPOT 50 SX FROM 600 TO 450 FT. TOH TO 40 FT & SPOT 10 SX FROM 40 TO 0 FT. CUT OFF CSG 3 FT BELOW GL & CAP. PERMANENTLY INSCRIBED WELL NAME AND DATE PLUGGED ON CAP. RDMO CSG. PULLERS.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor: SARGENT & HORTON PLUGGING

Address RT. 1, BOX 49BA, TYRONE, OKLAHOMA 73951-9731

License No. RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

SEP 29 1995

STATE OF KANSAS COUNTY OF SEWARD

CONSERVATION DIVISION
Wichita, Kansas

DAVID W. KAPPLE (Employee of Operator) or (xxxxxxx) of above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David W. Kapple

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 26th day of September, 19 95

L. MARC HARVEY
Notary Public - State of Kansas
My Commission Expires 6-12-99

L. Marc Harvey
Notary Public

My Commission Expires: _____