

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-129-20660 -0000

LEASE NAME Berryman Richfield Unit

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 14-3

NW NE          Ft. from S Section Line

         Ft. from E Section Line

SEC. 3 TWP. 33S RGE 41W (E) or (W)

COUNTY Morton

Date Well Completed         

Plugging Commenced 5-7-92

Plugging Completed 5-12-92

LEASE OPERATOR Merrico Resources, Inc.

ADDRESS P.O. Box 849 Ardmore, Oklahoma 73402

PHONE#(     ) 226-6700 OPERATORS LICENSE NO. 03408

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-7-92 (date).

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? Filed w/CP-1

Producing Formation          Depth to Top          Bottom          T.D. 5150

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1421	0
				5 1/2	5146	2730

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet each set.

- Set CTRP w/2 sks. of cement @ 4943
- Pump 50 sks. of cement from 1450 to 1350
- Pump 35 sks. of cement from 700 to 600
- Put 10 sks. of cement from 40 to 0 Cut off & cap 8 5/8 4' below ground level  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O. Box 506 Liberal, Kansas 67905-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Merrico Resources, Inc.

STATE OF Kansas COUNTY OF Morton, ss.

W. B. Curry, Jr.

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) W.B. Curry, Jr.


(Address) P.O. Box 849, Ardmore, Oklahoma 73402

SUBSCRIBED AND SWORN TO before me this 18th day of June 1992

Carl S. McNamee

Notary Public

My Commission Expires: 4/5/93



# GEARHART

# CEMENT BOND LOG

FILING NO.		COMPANY <u>LAOD PETROLEUM CORP</u>					
		WELL <u>B.R.U. 14-3</u>					
		FIELD <u>RICHFIELD</u>					
		COUNTY <u>MORTON</u>			STATE <u>KANSAS</u>		
		LOCATION <u>NW-SE</u>				Other Services	
		SEC <u>3</u>		TWP <u>33S</u>		RGE <u>41W</u>	
Permanent Datum <u>GL</u>		Elev. <u>3435</u>		KB <u>3446</u>		Elevations:	
Log Measured from <u>KB</u>		<u>11</u> Ft. Above Permanent Datum		DF			
Drilling Measured from <u>KB</u>				GL <u>3435</u>			
Date	<u>7-15-83</u>	Type Fluid in Hole		<u>WATER</u>			
Run No.	<u>ONE</u>	Dens.	Visc.				
Depth-Driller	<u>5150</u>	Max. Rec. Temp.					
Depth-Logger	<u>5096</u>	Est. Cement Top		<u>4742</u>			
Btm. Log Interval	<u>5088</u>	Equip.	Location	<u>7222</u>	<u>LIBERAL</u>		
Top Log Interval	<u>3901</u>	Recorded By		<u>JIM CAMPBELL</u>			
Open Hole Size	<u>7 7/8</u>	Witnessed By		<u>MR. BROWN</u>			
CASING REC.	Size	Wt/Ft	Grade	Type Joint	Top	Bottom	
Surface String	<u>8 5/8</u>				<u>SURF</u>	<u>1420</u>	
Prot. String							
Prod. String	<u>5 1/2</u>				<u>SURF</u>	<u>TD</u>	
Liner							
PRIMARY CEMENTING DATA							
STRING	Surface	Protection	Production	Liner			
Vol. of Cement	FIELD PRINT		<u>150.5X</u>				
Type of Cement			RECEIVED				
Additive			STATE CORPORATION COMMISSION				
Additive by %			APR 22 1984				
Retarder							
Retarder by %							
Wt. of Slurry			CONSERVATION DIVISION				
Water Loss			Wichita, Kansas				
Drill. Mud Type							
Drilling Mud Wt.							

FOLD HERE