

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-025-21,053 0000

LEASE NAME Harden Farms

WELL NUMBER 1-3

990 Ft. from S Section Line

990 Ft. from ~~SE~~ Section Line

SEC. 3 TWP. 34 RGE. 25 (E) or (W)

COUNTY Clark

Date Well Completed _____

Plugging Commenced 10/30/00

Plugging Completed 11/02/00

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Standard Operating, Inc.

ADDRESS 100 S Main, Suite 415-Wichita KS 67202

PHONE#(316) 264-7566 OPERATORS LICENSE NO. KLN 30029

Character of Well Gas

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/29/00 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top 5509' Bottom 5521' T.D. 5850'

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	669'	0
				4 1/2	5624'	5000'

DEC 12 2000

CONSERVATION DIVISION
Wichita Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Mix and pump 20 sacks cement, 1 sack of hulls, displ. with mud from 5521' to 5300'. Laid down 4 1/2" from 5000' to 1200'. Circulate hole with mud. Pump 50 sacks cement from 1200' to 1000'. Pulled to 700'. Pumped 50 sacks cement. from 700' to 500'. Pulled to 40'. 10 sacks cement 40' to 0.

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O. Box 506- Liberal, KS 67905-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: STANDARD OPERATING, INC.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.


David B. Pauly, Jr., President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) David B. Pauly
(Address) 100 South Main Suite 415
Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 8th day of December, 192000

Sally R. Byers
Notary Public

My Commission Expires December 6, 2004



Form CP-
Revised 03-8
MB