

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-18299-00-00
Spot: S2SWSE Sec/Twnshp/Rge: 12-11S-18W
330 feet from S Section Line, 1980 feet from E Section Line
Lease Name: HADLEY A TWIN Well #: 6
County: ELLIS Total Vertical Depth: 3442 feet

Operator License No.: 30606 String Size Depth (ft) Pulled (ft) Comments
Op Name: MURFIN DRILLING CO., INC. PROD 5.5 3441 150 SX
Address: 250 N WATER STE 300 SURF 8.625 135 125 SX
WICHITA, KS 67202

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/19/2015 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: CRAIG HERTEL Company: MURFIN DRILLING CO., INC. Phone: (785) 623-0123

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement, 6 sx gel and 500 # hulls.
DV Tool at 1083 w/300 sx cement. CIBP at 2750', 3110' and 3300'. PBTD 3393'. Perforations: 2787' - 3214' OH ARB.

KCC WICHITA

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/19/2015 12:45 PM KCC Agent: PAT STAAB

MAR 02 2015
RECEIVED

Actual Plugging Report:

Murfin ran in hole with tubing to 2709' and pumped 6 sx gel followed by 50 sx cement w/250 # hulls mixed in. Pulled tubing to 1669'. Quality rigged to tubing and mixed and pumped 165 sx cement w/250 # hulls to circulate cement up 5 1/2" casing. Pulled tubing. Topped off 5 1/2" casing with 35 sx cement. Rigged to 8 5/8" casing with instant pressure.

GPS: 39.10392 -099.26558
303' FSL 1874' FEL
SW SE SW SE

Perfs:

Top	Bot	Thru	Comments
3207	3214		
3178	3187		
3136	3146		
3076	3089		
3043	3064		
3020	3026		
2940	2966		
2905	2910		
2787	2851		

Remarks: QUALITY OILWELL CEMENTING TICKET # 1391

Plugged through: TBG

MAR 04 2015
CKM

District: 04

Signed


(TECHNICIAN)

CM

FEB 20 2015