

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-03197-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 6-15S-13W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: BERRICK Well #: 1
County: RUSSELL Total Vertical Depth: 3304 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3294		75 SX
SURF	8.625	226		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/18/2015 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: STAN FROETSCHNER Company: MURFIN DRILLING CO., INC. Phone: (800) 433-9047

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement w/500 # hulls.

KCC WICHITA
MAR 02 2015
RECEIVED

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/18/2015 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

02/17/2015- Unit rigged up, ran casing jar in and stacked out 20' down. Picked up tubing and worked through bridge. Hit the next bridge at 200'. Worked through to 1585' and hit solid bridge. Worked on it and could not make any hole. Pulled tubing. Picked up sand pump and samples were few having iron shavings in them (like casing).
02/18/2015-Perforated at 200' and 865'. Ran tubing to 1500' and pumped 180 sx cement. Circulated cement out of the backside. POOH. Hooked to casing and pumped 45 sx cement. Circulated cement out of the braden head at 400 psi. Shut in both sides.

GPS: 38.75011 -098.80010

Perfs:

Top	Bot	Thru	Comments
3295	3304		
3042	3060		
3033	3038		

Remarks: QUALITY CEMENTING TICKET # 1151

Plugged through: TBG

MAR 04 2015 CM

District: 04

Signed

Ray AO

(TECHNICIAN)

CM

FEB 20 2015