

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-05724-00-00
Spot: NWSESE Sec/Twnshp/Rge: 9-15S-12W
990 feet from S Section Line, 990 feet from E Section Line
Lease Name: ZEMAN LKC UNIT Well #: 205
County: RUSSELL Total Vertical Depth: 3283 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3281		125 SX
SURF	8.625	754		400 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/12/2015 10:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Revd. from: STAN FROETSCHNER Company: MURFIN DRILLING CO., INC. Phone: (785) 483-1197

Proposed Plugging Method: Ordered 425 sx 60/40 pozpix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/12/2015 3:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 1350', 750' and 350'. Ran tubing to 3050' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2050' and pumped 100 sx cement. Pulled tubing to 1150' and pumped 110 sx cement. Cement circulated out backside. Shut in and pumped an additional 75 sx cement. Circulated cement out the braden head. POOH. Hooked to braden head and pumped 15 sx cement. Circulated cement out of casing. Shut in and pressured up to 300 psi. Shut in braden head.

GPS: 38.75768 -098.65540

Perfs:

Top	Bot	Thru	Comments
3059	3070		
3043	3046		

Remarks: QUALITY CEMENTING TICKET # 1089

Plugged through: TBG

CM MAR 04 2015

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

KCC WICHITA

FEB 16 2015

RECEIVED

FEB 13 2015