

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-039-21211-00-00  
Spot: SENENWNE Sec/Twnshp/Rge: 28-1S-28W  
385 feet from N Section Line, 1600 feet from E Section Line  
Lease Name: VOTAPKA Well #: 1-28  
County: DECATUR Total Vertical Depth: 4250 feet

Operator License No.: 34418  
Op Name: PRAIRIE FIRE PETROLEUM, LLC  
Address: PO BOX 38  
NORTON, KS 67654

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	265		195 sx

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/13/2015 12:00 AM  
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.  
Proposal Rcvd. from: LARRY Company: VAL ENERGY, INC. Phone: (620) 804-0097

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

KCC WICHITA  
MAR 02 2015

RECEIVED

Plugging Proposal Received By: DARREL DIPMAN Witness Type: NONE  
Date/Time Plugging Completed: 02/13/2015 8:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

1st plug @2350 w/50 sx  
2nd plug @1550 w/100 sx  
3rd plug @315 w/50 sx  
4th plug @40 w/10 sx  
  
Rathole 30 sx Mousehole 15 sx

Remarks: CONSOLIDATED

Plugged through: DP

MAR 04 2015  
CKM

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM

FEB 18 2015