

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-24762-00-00  
Spot: NWNE Sec/Twnshp/Rge: 29-19S-14W  
660 feet from N Section Line, 1980 feet from E Section Line  
Lease Name: ALDRICH Well #: 3  
County: BARTON Total Vertical Depth: 2350 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S MAIN ST  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2348	860	95 SX
SURF	8.625	859		425 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/29/2015 8:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: GRADY BOLDING Company: GRADY BOLDING Phone: (620) 564-2240

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Shallow Gas well.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/02/2015 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped off with cement. Couldn't get casing cut at 1500'. Decided to perforate at 1548'. Ran tubing to 1500' and pumped 40 sx cement. Pulled tubing out of well. Cut casing at 860' and pumped 100 sx cement. Pulled casing to 350'. Circulated cement to surface with 160 sx cement. Pulled casing out and hole stayed full.

GPS: 38.37440 -098.89179

Perfs:

Top	Bot	Thru	Comments
2246	2250		
1872	1878		
1827	2250		
1746	1752		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

*CSG*  
MAR 04 2015

District: 04

Signed \_\_\_\_\_

*Bruce Rodie*

KCC WICHITA

(TECHNICIAN)

CM

FEB 06 2015

FEB 18 2015

Form CP-2/3

RECEIVED