

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-05530-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 26-13S-16W
2310 feet from N Section Line, 330 feet from W Section Line
Lease Name: DORTLAND TWIN Well #: 1
County: ELLIS Total Vertical Depth: 3447 feet

Operator License No.: 3911

Op Name: RAMA OPERATING CO., INC.

Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3447		150 SX
SURF	8.625	270		175 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 02/13/2015 9:00 AM

Plug Co. License No.: 34069

Plug Co. Name: BASIC ENERGY SERVICES, LP

Proposal Rcvd. from: ROBIN AUSTIN

Company: RAMA OPERATING/KIZZAR WELL Phone: (620) 234-5191

Proposed Plugging Method: Ordered 290 sx 60/40 pozmix 4% gel cement, 11 sx gel and 500 # hulls.
Perforations: 3218' - 3474' LKC
DV Tool at 1050' w/370 sx cement.

Plugging Proposal Received By: RICHARD WILLIAMS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 02/13/2015 3:15 PM

KCC Agent: PAT STAAB

Actual Plugging Report:

Kizzar Well Service ran in hole to 3200' and pumped 11 sx gel followed by 75 sx cement w/300 # hulls mixed in. Pulled tubing to 1624' and mixed and pumped 150 sx cement w/200 # hulls mixed in to circulate cement to pit area. Pulled tubing and topped off 5 1/2" casing w/5 sx cement. Hole standing full. Rigged to 8 5/8" casing and pumped 2 sx cement to pressure with 150 psi. Shut in pressure 150 psi.

GPS: 38.89425 -099.07571
3074' FSL 4970' FEL
NW SW SW NW

Perfs:

Top	Bot	Thru	Comments
3218	3474		

Remarks: BASIC ENERGY SERVICES TICKET # 12118

Plugged through: TBG

JKS
MAR 04 2015

District: 04

Signed



(TECHNICIAN)

CM

KCC WICHITA

FEB 25 2015

RECEIVED

FEB 18 2015