

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-19217-00-00
Spot: NESENE Sec/Twnshp/Rge: 11-16S-12W
3630 feet from S Section Line, 330 feet from E Section Line
Lease Name: THILL Well #: 1
County: BARTON Total Vertical Depth: 3373 feet

Operator License No.: 30275
Op Name: REDDIG, ROGER L. DBA CLOVER OIL
Address: PO BOX 173
RUSSELL, KS 67665

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 4.5 | 3348 | | 215 SX |
| SURF | 8.625 | 250 | | 100 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/18/2015 11:30 AM
Plug Co. License No.: 33385 Plug Co. Name: J & M WELL SERVICING, INC.
Proposal Rcvd. from: ROGER REDDIG Company: CLOVER OIL COMPANY Phone: (785) 483-3085

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RAY DINKEL
Date/Time Plugging Completed: 02/18/2015 4:00 PM

Witness Type: COMPLETE (100%)
KCC Agent: RAY DINKEL

KCC WICHITA

MAR 02 2015

RECEIVED

Actual Plugging Report:

Casing was parted at 2340'. Could not get back into the bottom. Well had been abandoned in 2008.
02/18/2015- Perforated at 200', 780' and 1250'. Ran tubing to 2300' and pumped 100 sx cement w/100 # hulls. Well started to circulate fluids out the backside. Pulled tubing to 850' and pumped 75 sx cement. Cement circulated out of the backside. POOH. Hooked to braden head and pumped 45 sx cement. Cement circulated out of the casing. Shut in with 150 psi.

GPS: 38.67667 -098.60983

Remarks: QUALITY CEMENTING TICKET # 1070

Plugged through: TBG

MAR 04 2015 JMS

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

FEB 20 2015