

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-20421-00-00
Spot: NE Sec/Twnshp/Rge: 34-12S-17W
330 feet from N Section Line, 990 feet from E Section Line
Lease Name: SCHMEIDLER Well #: 2D
County: ELLIS Total Vertical Depth: 3649 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>6037</u>	<u>PROD</u>	<u>5.5</u>	<u>3617</u>		<u>150 SX</u>
<u>Op Name: STAAB OIL CO., A GENERAL PARTNER</u>	<u>SURF</u>	<u>8.625</u>	<u>215</u>		<u>150 SX</u>

Address: 1607 HOPEWELL RD
HAYS, KS 67601

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/11/2015 9:30 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: FRANCIS C. STAAB Company: STAAB OIL CO. Phone: (785) 625-5013

Proposed Plugging Method: Ordered 305 sx 60/40 pozmix 4% gel cement, 12 sx gel and 500 # hulls. Perforated at 1850', 1275' and 750'

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/11/2015 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report: _____ Perfs: _____

Ran tubing to 3500' and pumped 12 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1850' and pumped 180 sx cement w/200 # hulls to circulate cement to surface. Pulled all tubing and topped off 5 1/2" casing w/30 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pumped 5 sx cement. Shut in pressure 300 psi.

Remarks: GLOBAL TICKET # 1606

Plugged through: TBG

MAR 04 2015
CKM

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

cm

KCC WICHITA

FEB 18 2015

RECEIVED

Form CP-2/3

FEB 13 2015