

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25596-00-00
Spot: SWSWNENW Sec/Twnshp/Rge: 28-20S-11W
1177 feet from N Section Line, 1486 feet from W Section Line
Lease Name: HAGEN B Well #: 1
County: BARTON Total Vertical Depth: 3410 feet

Operator License No.: <u>5030</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>VESS OIL CORPORATION</u>	PROD	5.5	3409	2018	125 SX
Address: <u>1700 WATERFRONT PKWY BLDG 500</u> <u>WICHITA, KS 67206</u>	SURF	8.625	522		350 SX
	T1	2.375	3267		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/10/2015 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: LAVERNE BROWN Company: VESS OIL Phone: (620) 791-7048

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/10/2015 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped off with cement. Cut casing at 2018'. Pulled casing to 1300' and pumped 125 sx cement w/200 # hulls. Pulled casing to 900' and pumped 60 sx cement w/100 # hulls. Pulled casing to 600 and pumped 50 sx cement w/100 # hulls. Pulled casing to 300'. Circulated cement to surface w/70 sx cement. Pulled casing. Hole stayed full.

GPS: 38.28681 -098.54849

Perfs:

Top	Bot	Thru	Comments
3336	3341		
3136	3142		
3120	3124		
3116	3126		
3094	3100		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

MAR 04 2015 ²⁰¹⁵

District: 04

Signed

Bruce Rodie
(TECHNICIAN)

CM

KCC WICHITA

FEB 11 2015

FEB 25 2015

RECEIVED