

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19240-00-00
Spot: NWNWNWNE Sec/Twnshp/Rge: 30-26S-5E
4989 feet from S Section Line, 2377 feet from E Section Line
Lease Name: KOGLER Well #: 1
County: BUTLER Total Vertical Depth: 2648 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.1875	2550		0 SX
SURF	6.825	2280		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/15/2014 11:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: AS PER KCC RULES & REGS

KCC WICHITA
MAR 02 2015
RECEIVED

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 12/15/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2535', CIRCULATED HOLE CLEAN, CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 75 SXS 60/40 POZMIX 4% GEL 2% CC & DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT PLUG @ 1841'. RIH W/ TBG @ 1200', CONSOLIDATED MIXED & PUMPED 25 SXS 60/40 POZMIX 4% GEL 2% CC & DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT PLUG @ 1016'. RIH W/PACKER & TBG @ 30', WELL CIRCULATED IMMEDIATELY TO SURFACE. PULLED TBG & PACKER. RIH ON WIRELINE SHOT SQUEEZE HOLES 270'-271' (4 HOLES). RIH W, TBG @ 310', CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 75 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE, CEMENT CIRCULATED. CONSOLIDATED CEMENT TICKET #48494 & 48437.

Perfs:

Top	Bot	Thru	Comments
2550	2648	OH	

Remarks:

Plugged through: TBG

MAR 04 2015 *JM*

District: 02

Signed

Duane Krueger
(TECHNICIAN)

JK