

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19555-00-01
Spot: NESENE Sec/Twnshp/Rge: 35-27S-4E
3640 feet from S Section Line, 327 feet from E Section Line
Lease Name: SKAER A OWWO Well #: 19
County: BUTLER Total Vertical Depth: 2563 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 7 | 2506 | | 30 SX |
| SURF | 8.625 | 2069 | | 0 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/15/2014 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Revd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: Per KCC District #2 instructions

KCC WICHITA
MAR 02 2015

RECEIVED

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 12/17/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2504', CIRCUALTED HOLE CLEAN, CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL 4% CC & DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 2191'. RIH W/TBG @ 2100', CONSOLIDATED MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL 2% CC & DISPLACED IN CASING. 12-16-2014, TAGGED CEMENT PLUG @ 1581'. RIH W. TBG @ 1000', CONSOLIDATED MIXED & PUMPED 35 SXS CLASS A COMMON 3% CC. WAITED 2 HOURS, TAGGED CEMENT PLUG @ 393'. PRESSURED CAISNG @ 500#, HELD OK. 12-17-2014, RIH ON WIRELINE SHOT SQUEEZE HOLES 270'-271', (4 HOLES). SWEDGED INTO 7" CASING, CONSOLIDATED MIXED & PUMPED 375 SX 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. HOOKED UP INTO 13" CASING, CONSOLIDATED MIXED & PUMPED 75 SXS BETWEEN 13" & 8.625" SURFACE. SIP 250#. CONSOLIDATED CEMENT TICKET #48697.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2522 | 2528 | OH | |

Remarks:

Plugged through: TBG

MAR 04 2015 *DM*

District: 02

Signed

Duane Krueger
(TECHNICIAN)

JK